

---

# Division 10

---

**SECTION 10100****MARKERBOARDS AND TACKBOARDS****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Marker Boards
- B. Tack Boards

**1.02 SUBMITTALS**

- A. Submittals
  - 1. Submit under provisions of Section 01300.
  - 2. Product Data: Indicate material types, finishes and sizes, and installation details and requirements.

**1.03 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience.

**1.04 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the Work with Painting.

**PART 2 - PRODUCTS****2.01 MATERIALS**

- A. Markerboards shall be "total erase" with hard, durable surface that does not require the use of cleaners, heavy gauge satin finish anodized aluminum frame with full size marker tray with protective end caps.
  - 1. Sizes:
    - a. Program areas – 8 feet by 4 feet
    - b. Administration, Staff Support, Booking, Food Service and Medical areas – 4 feet by 4 feet
- B. Tackboards shall be 1/8" thick, high grade cork with 3/8" thick fiberboard core backing, solid aluminum frame.
  - 1. Size: All areas – 4 feet by 4 feet.
- C. Manufacturers providing products meeting required quality standards:
  - 1. Aarco Products, Inc.
  - 2. Claridge Products and Equipment, Inc.
  - 3. GPC, Education Products Division

4. Other manufacturers as approved by Owner's Project Manager

## **2.03 ACCESSORIES**

- A. All wall anchors, blocking, fasteners and attachment devices as required for a complete installation.

## **PART 3 - EXECUTION**

### **3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that prepared mounting surfaces have been painted and are ready to receive work.

### **3.02 INSTALLATION**

- A. Install in accordance with manufacturer's printed instructions.

### **3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**

**SECTION 10165****LAMINATED PLASTIC TOILET COMPARTMENTS AND URINAL SCREENS****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Laminated toilet compartments and urinal screens(public and staff toilets)

**1.02 RELATED SECTIONS**

- A. Section 09300 – Tile Work
- B. Section 09900 – Painting

**1.02 SUBMITTALS**

- A. Submittals
  - 1. Submit under provisions of Section 01300.
  - 2. Product Data: Indicate material types, finishes and sizes, and installation details and requirements.

**1.03 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum three years documented experience.

**1.04 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the Work with installation of interior finishes.

**PART 2 - PRODUCTS****2.01 MATERIALS**

- A. Toilet compartments shall be floor-mounted overhead-braced type, flush panel.
- B. Urinal screens shall be floor mounted type.
- C. Partition board material shall be Industrial Grade 45 lb. density particleboard.
- D. Plastic laminate NEMA LD-3-1975, Grade GP 50, selected from manufacturer's standard colors
- E. Hinges and bracket hardware shall be heavy duty cast chrome plated non-ferrous type.
- F. One (1) collapsible security type coat hook shall be provided on the inside of each partition door.
- G. Manufacturers providing products meeting required quality standards:
  - 1. Ampco Products, Inc.
  - 2. Bobrick Partitions, Bobrick Washroom Equipment, Inc.
  - 3. General Partitions Mfg. Corp.

4. Metpar Corp.
5. Other manufacturers as approved by the Owner's Project Manager.

## **2.02 ACCESSORIES**

- A. All wall anchors, blocking, fasteners and attachment devices as required for a complete installation.
- B. All floor and wall anchors, blocking, fasteners and attachment devices as required for a complete installation.

## **PART 3 - EXECUTION**

### **3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that floor and wall surfaces are ready to receive work, including any necessary blocking or reinforcement required for a secure installation.

### **3.02 INSTALLATION**

- A. Install in accordance with manufacturer's written instructions.

### **3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**

**SECTION 10211****FIXED METAL WALL LOUVERS****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Fixed louvers and frames.
- B. Bird screening.

**1.02 RELATED SECTIONS**

- A. Section 07900 - Joint Sealers.

**1.03 REFERENCES**

- A. AMCA 500 (Air Movement Control Association) - Test Method for Louvers, Dampers, and Shutters.
- B. ASTM A526 - Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process, Commercial Quality.

**1.04 PERFORMANCE REQUIREMENTS**

- A. Louver: To permit 50 percent free area.

**1.05 SUBMITTALS**

- A. Submittals
  - 1. Submit under provisions of Section 01300.
  - 2. Shop Drawings: Indicate louver layout plan and elevations, opening and clearance dimensions, tolerances; head, jamb and sill details; blade configuration, screens, blankout areas required, and frames.
  - 3. Product Data: Provide data describing design characteristics, maximum recommended air velocity, design free area, materials and finishes.
  - 4. Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.

**1.06 QUALITY ASSURANCE**

- A. Perform Work in accordance with AMCA Certification for louvers.

**1.07 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing Products specified in this section with minimum three years documented experience.

**1.08 FIELD MEASUREMENTS**

- A. Verify that field measurements are as indicated on shop drawings.

**1.09 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the Work with installation of masonry flashings.

**1.10 WARRANTY**

- A. Provide twenty year warranty under provisions of Section 01700.

**PART 2 - PRODUCTS****2.01 MATERIALS**

- A. Steel Sheet: ASTM A526, galvanized to G90 zinc coating, prefinished with shop applied flouropolymer finish.

**2.02 SCREENS**

- A. Bird Screen: Interwoven wire mesh of steel 0.063 inch diameter wire, 1/2 inch open weave, square design.

**2.03 ACCESSORIES**

- A. Accessories
  - 1. Fasteners and Anchors: Galvanized steel type.
  - 2. Primer: Zinc chromate, alkyd type.
  - 3. Flashings: Of same material as louver frame.
  - 4. Sealants: Type specified in Section 07900.

**2.04 FABRICATION**

- A. Fabrication
  - 1. Louver Panel Thickness: 4 inches deep.
  - 2. Louver Blade Design: Sloped at 45 degrees; reinforced with intermediate stiffeners, material thickness of 12 gage minimum, integral and lateral rain water stops positioned on blade.
  - 3. Louver Frame: Channel shape, welded corner joints, material thickness of 12 ga. minimum.
  - 4. Intermediate Mullions: Concealed formed steel, profiled to suit louver frame.
  - 5. Head and Sill Flashings: Roll formed to required shape, single length in one piece per location.
  - 6. Screens: Install screen mesh in shaped frame, reinforce corner construction, shop install to louver with fasteners.

**2.05 FINISHES**

- A. Exterior Steel Surfaces: Prepainted finish of color to be selected.
- B. Interior Steel Surfaces and Screens: Prepainted finish of color to be selected.

**PART 3 - EXECUTION****3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that prepared openings and flashings are ready to receive work and opening dimensions are as indicated on shop drawings.

**3.02 INSTALLATION**

- A. Installation
  - 1. Install louver assembly in accordance with manufacturer's instructions.
  - 2. Install louvers level and plumb.
  - 3. Install flashings and align louver assembly to ensure moisture shed from flashings and diversion of moisture to exterior.
  - 4. Secure louvers in opening framing with concealed fasteners, removable for maintenance purposes.
  - 5. Install bird screen and frame to interior of louver. Hinge screens for access.
  - 6. Install perimeter sealant and backing rod in accordance with Section 07900.

**3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**



**SECTION 10270  
ACCESS FLOORING****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Access floor systems in Central Control Room and Housing Control Rooms

**1.02 RELATED SECTIONS**

- A. Division 9 Finishes
- B. Division 15 Mechanical
- C. Division 16 Electrical
- D. Division 17 Security Electronics

**1.03 SUBMITTALS**

- A. Submit under provisions of Section 01300.
- B. Product Data: Indicate material types, finishes and sizes, and installation details and requirements.

**1.04 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum five years documented experience.

**1.05 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the Work with Mechanical, Electrical, and Security Electronics sub-contractors

**1.06 PERFORMANCE REQUIREMENTS**

- A. Heavy duty access floor panel capable of supporting a 3,000 lb. single caster load. Panel shall have an ultimate load rating of 10,000 lb. and a concentrated load rating of 3,000 lb. with permanent set .010 or less.
- B. Meet seismic bracing requirements as required by applicable building codes and regulations for Bozeman, MT.

**1.07 SUBMITTALS**

- A. Submittals
  - 1. Submit under provisions of Section 01300.

2. Shop Drawings: Indicate understructure and panel layout plan, cutout locations to accommodate cable penetrations and service outlets, and fabrication and construction details.
3. Product Data: Provide data describing design characteristics, maximum recommended loadings, materials and finishes.
4. Manufacturer's Certificate: Certify that Products meet or exceed specified requirements.

#### **1.08 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing Products specified in this section with minimum three years documented experience.

#### **1.09 FIELD MEASUREMENTS**

- A. Verify that field measurements are as indicated on shop drawings.

### **PART 2 - PRODUCTS**

#### **2.01 MATERIALS**

- A. Products shall meet or exceed performance criteria stipulated above.
- B. Manufacturers providing products meeting required quality standards:
  1. AMICO-Genesis, Alabama Metal Industries Corporation
  2. ASM Modular Systems, Inc.
  3. Interface Architectural Resources, Inc.
  4. Tate Access Floors, Inc.
  5. Other manufacturers as approved by the Owner's Project Manager.

#### **2.02 ACCESSORIES**

- A. Provide all fasteners, anchors, connection devices, and other accessories necessary for a complete installation.

#### **2.03 FINISHES**

- A. Factory-prepared high pressure laminate, carpet tile or VCT as selected by Owner's Project Manager from manufacturer's standard products and colors.

### **PART 3 - EXECUTION**

#### **3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that prepared substrate is ready to receive work and that technical infrastructure systems are in place and ready for access floor installation.

**3.02 INSTALLATION**

- A. Only installers licensed or approved by the access floor system manufacturer are acceptable.
- B. Install the system in accordance with manufacturer's written instructions. Insure that the assembly is properly grounded.

**3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**

**SECTION 10400****IDENTIFYING DEVICES****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Room Signage: All rooms and spaces including restrooms, offices, support spaces, housing pods and individual cells.
- B. Directional and regulatory signs including but not limited to exit signs and handicapped accessibility symbols..
- C. Building directory (interior)
- D. Building identification sign (exterior)

**1.02 RELATED SECTIONS**

- A. Division 3 – Concrete
- B. Section 0900 – Painting
- C. Division 16 – Electrical

**1.03 PERFORMANCE CRITERIA**

- A. Signage must comply with all applicable ADA requirements.

**1.04 SUBMITTALS**

- A. Submittals
  - 1. Submit under provisions of Section 01300.
  - 2. Shop Drawings: Indicate layout diagrams including elevations, showing dimensions and (if applicable) letter sizes and type faces, colors available, mounting heights and other installation details.
  - 3. Product Data: Provide data describing design characteristics and installation requirements.
  - 4. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

**1.05 QUALIFICATIONS**

- A. Manufacturer: Company specializing in manufacturing products specified in this section with minimum five years documented experience. Manufacturers of products meeting quality standards:
  - 1. Andco Industries Corporation
  - 2. ASI-Modulex
  - 3. Best Signs
  - 4. National Signage Affiliates
  - 5. Other manufacturers as approved by Owner's Project Manager

**1.06 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the installation of exit signs with electrical subcontractor; coordinate all work with painting and interior finishing trades.

**PART 2 - PRODUCTS****2.01 MATERIALS**

- A. Secure Areas (cells, dayrooms, dormitories, intake/booking/holding, any area in which detainees are not under constant supervision of detention staff):
  - 1. Pressure-sensitive vinyl letters adhered to wall, door frame or door surfaces as directed by Owner's representative. Size for easy visibility from the farthest point in the area where located.
- B. Staff and Public Areas (lobby, offices, spaces to which detainees do not have un-accompanied access):
  - 1. Room Identification and Information Signs – Synthetic material construction with raised graphics and Grade 2 braille (similar to Andco RA 1000 Sign Series).
    - a. Backplate – ¼" acrylic
    - b. Framed type sign
  - 2. Building Directory – Changeable letter display type (similar to Andco Type 20, composite board slotted and covered with a vinyl substrate. Changeable white letters, 3/8" height on black letterboard.
- C. Exterior Signs
  - 1. Building Identification Letters – Precision cut metal-laminated acrylic letters or reverse channel .090" aluminum letters, 8" high, to spell GALLATIN COUNTY DETENTION CENTER.
  - 2. Directional and Accessibility Signs
    - a. Handicapped Parking Signs – Post-mounted screened steel signs, 12" w x 18" h, with words "HANDICAPPED PARKING" and international handicapped symbol, white letters on blue background. Provide a total number of signs equal to 5% of total number of public and staff parking spaces.

**2.02 ACCESSORIES**

- A. Provide all mounting and attachment devices and accessories required for a complete installation.

**PART 3 - EXECUTION****3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that prepared substrates and surfaces to receive work are acceptable before proceeding with installation.

**3.02 INSTALLATION**

- A. Install signs, letters and devices in full accordance with manufacturer's written instructions.

**3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**

**SECTION 10500****LOCKERS****PART 1 - GENERAL****1.01 SECTION INCLUDES**

- A. Single tier (full height) metal lockers and benches in staff support areas.

**1.02 SUBMITTALS**

- A. Submittals
  1. Submit under provisions of Section 01300.
  2. Product Data: Provide data describing design characteristics, materials and finishes, and recommended installation methods.
  3. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.

**1.03 COORDINATION**

- A. Coordinate work under provisions of Section 01040.
- B. Coordinate the Work with installation of finishes.

**PART 2 - PRODUCTS****2.01 MATERIALS**

- A. Single Tier Metal Lockers
  1. 15" w x 18" d x 72" h with top shelf, coat rod, padlock attachment integral with handle, and number/name plate.
  2. Provide lockers in one or three frame wide sections.
  3. Provide closed-style bases, approx. 6" height, same color as lockers
  4. Color to be selected by Owner from manufacturer's standard color selection.
  5. Quality Standard: Lyon Workspace Products model No. 5062 series
- B. Benches
  1. Hardwood benches on painted steel pedestals.
  2. Quantity and lengths to be determined by Design-Builder as suitable for configuration of locker area.

**2.02 ACCESSORIES**

- A. Provide all attachment hardware, fastenings, parts and other accessories necessary for a complete installation.

**PART 3 - EXECUTION****3.01 EXAMINATION**

- A. Verify site conditions under provisions of Section 01040.
- B. Verify that prepared surfaces are ready to receive work.

**3.02 INSTALLATION**

- A. Lockers and benches are to be anchored to the floor and, in the case of lockers, attached to wall.

**3.03 CLEANING**

- A. Clean work under provisions of 01700.
- B. Clean surfaces and components.

**END OF SECTION**



**SECTION 10520****FIRE EXTINGUISHERS AND CABINETS****PART 1 - GENERAL****1.01 SUBMITTALS**

- A. Product data: Indicate material types, finishes and sizes, lettering styles available, fabrication and installation details and requirements.

**1.02 JOB CONDITIONS**

- A. Protection: Protect pre-finished surfaces from damage or staining. Provide protective covering following installation until Date of Substantial Completion.
- B. Coordinate installation of fire extinguisher cabinets to be built into building structure. Secure templates or lay out to rough dimensions provided by cabinet manufacturer.

**PART 2 - PRODUCTS**

- A. Acceptable manufacturers:
  - 1. Elkhart Brass Mfg. Co.
  - 2. J.L. Industries, Inc.
  - 3. Larsen's Manufacturing Company.
  - 4. Norris Industries.
  - 5. Standard Fire Equipment Div./Zurn Industries, Inc.
  - 6. Other manufacturers as approved by Owner's Project Manager.
- B. Halon 1211 extinguisher: Five lbs., rated 10-B:C. Extinguisher shall be complete with funnel shaped nozzle and pressure gauge.
- C. Dry chemical extinguisher: Five lbs., rated d2A-10B:C. Extinguisher shall be complete with nozzle and pressure gauge.
- D. Fire extinguisher cabinets:
  - 1. Type: Solid panel comparable to Larsen's "Occult" Series.
  - 2. Sizes: As required for extinguisher.
  - 3. Cabinet interior material and finish: Minimum 18 ga. steel.
  - 4. Door and trim material: Minimum 20 ga. steel baked-on prime coat.
  - 5. Hardware: Door shall be equipped with full length piano hinge and manufacturer's standard pull.
  - 6. Lettering: Provide pressure sensitive lettering "FIRE EXTINGUISHER" for each cabinet.
- E. Wall bracket: Extinguisher manufacturer's standard bracket supporting extinguisher at top and bottom and holding extinguisher off finished wall surfaces.

**PART 3 - EXECUTION****3.01 INSTALLATION**

- A. Install units in accordance with manufacturer's product data, plumb, level and true to line and location.

- B. Secure fire extinguisher cabinets in walls, plumb and level, attached to structure. Provide one extinguisher for each cabinet. Set at 5'-6" to top of cabinet. Charge and install extinguisher just prior to Date of Substantial Completion.
- C. Install bracket mounted extinguisher at 5'-6" from finish floor to top of extinguisher. Charge and install extinguisher just prior to Date of Substantial Completion.

**END OF SECTION**

**SECTION 10800****TOILET ACCESSORIES AND  
MISCELLANEOUS EQUIPMENT****PART 1 - GENERAL****1.01 SUBMITTALS**

- A. Product data: Include catalog cuts and data sheets indicating size, material and finish, complete parts list and installation procedures for each accessory.
- B. Samples: Submit one actual sample of each accessory, if requested by Owner's Project Manager. Upon acceptance, samples will be returned for incorporation into project.

**1.02 JOB CONDITIONS**

- A. Protection: Maintain manufacturer's protective covering on accessories until final clean-up of installation.
- B. Coordinate this work with work of other trades for setting built-in anchoring devices and to insure correct opening sizes for recessed accessories.

**1.03 QUALITY CRITERIA**

- A. All accessories except security items shall be the products of one manufacturer. Keyed accessories shall be keyed alike.

**1.04 WARRANTY**

- A. Mirrors: Warrant mirrors for five years against silver spoilage.

**PART 2 - PRODUCTS****2.01 ACCEPTABLE MANUFACTURERS**

- A. Bobrick Washroom Equipment, Inc. manufactures products of the acceptable quality standard.
- B. Substitutions: Under provisions of Section 01600.

**2.02 TOILET ACCESSORY / MISCELLANEOUS EQUIPMENT LEGEND**

- A. The Design-Builder shall prepare drawings indicating the following toilet accessories and miscellaneous equipment as required for a complete installation:
  - 1. Wall-mounted Grab Bar: Bobrick #B-6806.99
  - 2. Surface Mounted Toilet Paper Holder: Bobrick #B 66997.60
  - 3. Surface Mounted Sanitary Napkin Disposal: Bobrick #B-254
  - 4. Surface Mounted Paper Towel Dispenser/Disposal (small capacity): Bobrick #B-3699
  - 5. Surface Mounted Paper Towel Dispenser/Disposal (Large Capacity): Bobrick B-3604-P
  - 6. Wall Mounted Soap Dispenser #817699
  - 7. 1'-6"W x 3'-0"H Mirror: Bobrick #B-165 1836
  - 8. Robe/Coat Hook: Bobrick #B-682
  - 9. Recessed Paper Towel Dispenser (Large Capacity) - Bobrick B-363
  - 10. Mop Hanger: Bobrick B-223 x 36
  - 11. Security Grab Bar: Bobrick #813220-24
  - 12. Security Grab Bar: Bobrick #813220-36
  - 13. Security Grab Bar: Bobrick #813220-42

14. 10" x 11-1/2" Cell Mirror: See Section 11190 - Detention Equipment
15. 15. Recessed Security Toilet Paper Holder: See Section 11190 - Detention Equipment
16. Security Clothing Hook: See Section 11190 - Detention Equipment
17. Double Floor Mounted Bunk. - See Section 11190 - Detention Equipment
18. Floor-Mounted Steel Desk - See Section 11190 - Detention Equipment
19. Floor-Mounted Steel Seat - See Section 11190 - Detention Equipment
20. Wall-Mounted TV Support- See Section 11190 - Detention Equipment
21. Plastic Armchair - See Section 11190 - Detention Equipment
22. Floor Mounted Dayroom Table with (4) Attached Stools - See Section 11190 - Detention Equipment
23. Floor Mounted Dayroom Table with (8) Attached Stools - See Section 11190 - Detention Equipment
24. Video Visitation Equipment – See Section 17600 - Video Visitation Systems
25. Break-A-Way Curtain and Hardware – Imperial Fastener Company ceiling-mounted track # IFC-69.

### **PART 3 - EXECUTION**

#### **3.01 INSPECTION**

- A. Verify openings scheduled to receive recessed or semi-recessed accessories for correct dimensions, depth, plumbness of blocking or frames, and preparations that would affect installation of accessories.

#### **3.02 INSTALLATION**

- A. Install accessories level, plumb and in indicated location. Installation methods shall be as indicated in manufacturer's product data for substrates encountered.
- B. Mounting heights: Except as otherwise indicated, heights are given above finish floor (A.F.F.) to top of accessory.
  1. Combination towel dispenser and waste: 5'-0".
  2. Multipurpose unit: 3'-10" A.F.F. to towel dispenser.
  3. Feminine napkin/tampon dispenser: 3'-4" A.F.F. to coin slot.
  4. Feminine napkin disposal: 1'-2" A.F.F. to bottom of unit.
  5. Paper towel dispenser: 4'-6".
  6. Toilet tissue dispenser: 2'-6".
  7. Multi-roll toilet tissue dispenser: 2'-6".
  8. Mop and broom holder: 6'-0".
  9. Grab bars: 2'-9" A.F.F. to centerline.
  10. Soap dish/grab bar: 4'-6" A.F.F. to centerline.
  11. Mirrors
  12. Tilting mirrors: 5'-6".
- C. Secure grab bars to metal or wood stud partition by direct attachment to studs or blocking between studs.
- D. Attach grab bars to masonry or concrete walls using stainless steel bolts or screws and metal expansion shields.
- E. Attach grab bars to toilet partitions using wing tapped steel spacers and stainless steel machine screws. Where grab bar is attached to one side of partition only, spacer shall have minimum 16 ga. satin finish stainless steel back-up plate.
- F. Conceal evidence of drilling, cutting and fitting to adjacent finishes.
- G. Use TORX security screws to fasten all accessories mounted to masonry walls.

- H. Weld snap flange to all grab bars fastened to masonry walls.
- I. Install ceiling mounted break-a-way privacy curtain as shown in manufacturer's written instructions for installation required.
  - 1. Follow manufacturer's written instructions for installation in a security facility.
  - 2. Install ceiling track using non-removable security fasteners.

### **3.03 ADJUST AND CLEAN**

- A. Adjust operating components of accessories for proper operation.
- B. Clean and polish exposed surfaces just prior to Date of Substantial Completion.
- C. Delivery accessory schedule, keys and parts manual as part of contract close-out documents.

**END OF SECTION**